



Clamshell Dredging Sdn Bhd



At A Glance

Project:

Proposed Emergency Maintenance Dredging Works at Westports Conventional Berths B2—B4 Westports, Pulau Indah, Port Klang, Selangor.

Owner:

Westports Malaysia Sdn Bhd

Client:

Integrated Marine Works Sdn Bhd

Contract Sum:

RM 2,420,273.60

Contract Period:

17.06.2022 — 05.08.2022



P124 : Emergency Maint. Dredging Works at Westports, Klang

Dredging Works

Being the Top 10 most connected port in the world, Westports is able cater for cargo to be transported to any part of the world. The project is intended to carry out maintenance dredging by broadening its product base, including through 'logistical integration' and increasing its attractiveness to a wider range shippers and shipping lines.

Design Parameters :

Design Depth	: -15.5mCD & -17.5mCD
Disposal Location Distance	: approx. 13 nautical miles
Dredge Quantity	: 61,352.30 m ³ (Provisional)

Vessel Deployed :

No.	Equipment	Capacity	Quantity
1	Grab Dredger	16m ³	1
2	Non-propelled Split Hopper Barge	1,000m ³	2
3	Tug Boat	1,000bhp & 1,200bhp	2
4	Anchor Handling Tug	5T	1

